

CURING TIME EFFECT ON THE FRACTION OF ^{137}Cs FROM CEMENT-ION EXCHANGE RESINS-BENTONITE CLAY COMPOSITION[†]

UDC 546.36 : 615.463 + 666.32

Ilija Plećaš*, Slavko Dimović

Vinča Institute of Nuclear Sciences, P.O.BOX 522, 11001 Belgrade, Serbia

Abstract. *To assess the safety of disposal of radioactive waste material in cement, curing conditions and time of leaching radionuclides ^{137}Cs have been studied. Leaching tests in cement-ion exchange resins-bentonite matrix, were carried out in accordance with a method recommended by IAEA. Curing conditions and curing time prior to commencing the leaching test are critically important in leach studies since the extent of hydration of the cement materials determines how much hydration product develops and whether it is available to block the pore network, thereby reducing leaching. Incremental leaching rates $R_n[\text{cm/d}]$ of ^{137}Cs from cement-ion exchange resins-bentonite matrix after 240 days were measured. The results presented in this paper are examples of results obtained in a 30-year concrete testing project which will influence the design of the engineer trenches system for future central Serbian radioactive waste storing centre.*

Key words: *cement, radioactive waste, radionuclide, leaching, concrete*

1. INTRODUCTION

The objectives of immobilization are to convert the waste into forms which are: a) leach resistant, so that the release of radionuclides will be slow even in contact with flowing water; b) mechanically, physically and chemically stable for handling, transport and disposal.

Although cement has several unfavorable characteristics as a solidifying material, i.e. low volume reduction and relatively high leachability, it possesses many practical advantages: good mechanical characteristics, low cost, easy operation and radiation and thermal stability. It is generally assumed that the cement leachability of ^{137}Cs and other radionuclides can be reduced by adding minerals like bentonite and zeolite.

[†] Acknowledgment: This work was funded by the Ministry of Science and Technological Development of Serbia.

*Corresponding author. E-mail: iplecas@vinca.rs.

Received 16th November 2010; 16th December accepted 2010.

The resin has active groups in the form of electrically charged sites. At these sites ions of opposite charge are attached but may be replaced by other ions depending on their relative concentrations and affinities for the sites. Spent cation exchange resins containing ^{60}Co and represent a major portion of the solid radioactive waste in nuclear technology [1-5]. Cement is used as a solidification material for the storage of intermediate-level radioactive waste. However, the retention of radionuclides, especially cesium, in the cement matrix is negligible [1-3, 6-8]. The sorption of cesium on cement is low and diffusivity of cesium in the hydrated cement is high. Only when the cement is mixed with a material having a significant sorption capacity, normally bead or powdered ion exchange resins, is the leachability of cesium and cobalt from the cement matrix low enough to be acceptable.

Although cement has several unfavorable characteristics as a solidifying material, i.e. low volume reduction and relatively high leachability, it possesses many practical advantages: good mechanical characteristics, low cost, easy operation and radiation and thermal stability.

It is generally assumed that the cement leachability of ^{137}Cs and other radionuclides can be reduced by adding minerals like bentonite, vermiculite and clinoptilolite.

Curing time is critically important in leach studies since the extent of cement hydration determines how much hydration products develops and whether it is available to block the pore network, thereby reducing leaching [9]. The aim of this work is to describe leaching rate functional dependence of the cement curing time.

2. MATERIALS, METHODS AND EXPERIMENTAL CONDITIONS

The cement specimens were prepared from construction cement which is basically a standard Portland cement, PC-20-Z-45 MPa. The cement was mixed with saturated wet cation exchange resins (100 g of dry resins + 100 g of water containing ^{137}Cs) and bentonite clay (63% SiO_2 ; 18% Al_2O_3 ; 4% Fe_2O_3 ; 2.6% MgO and 3.3% CaO). The mixtures were cast into 50 mm diameter cylindrical molds with a height of 50 mm, which were then sealed and cured for 30 and 60 days prior to the leaching experiments. More than 100 different formulations of mortar form were examined to optimize their mechanical and sorption properties. In this paper we discuss three representative formulations. Grout composition formulas are shown in Table 1.

Table 1. Grout composition (calculated as grams for 1000 cm^3 of mixtures)

Materials	M_1	M_2	M_3
Cation exc. resins [g]	360	300	270
Portland cement [g]	1300	1360	1315
Water [mL]	260	280	300
Bentonite clay [g]	15	41	66
Initial activity A_0 [Bq ^{137}Cs per sample]	$8.0 \cdot 10^7$	$8.0 \cdot 10^7$	$8.0 \cdot 10^7$

Samples for leachability determination were prepared according to the IAEA standard procedure [6]. All prepared samples were stored in laboratory at ambient temperature (25 ± 3 °C) for 30 and 60 days curing time. Leachant was exchanged and analyzed for ra-

radioactivity after: 1, 2, 3, 4, 5, 6, 7 days, and thereafter every week for six months. After each leaching period the radioactivity in the leachant was measured using EG&G-ORTEC spectrometry system and software. The volume of the leachant in every leaching period was 200 cm^3 .

3. RESULTS

The results are expressed by incremental leaching rates $R_n[\text{cm/d}]$:

$$R_n = \frac{\sum a_n V}{A_0 S} \frac{1}{\sum t} \quad (\text{cm/d}) \quad (1)$$

where: a_n - the radioactivity of leached constituent during each leaching interval [Bq], A_0 - the specific radioactivity initially present in the specimen [Bq], S - the exposed surface area of the specimen [cm^2], V - the sample volume [cm^3], t - the duration of the leaching period [d].

Effects of curing time on the leach rate of ^{137}Cs from cement-waste matrix, for different grout compositions, are given in Tables 2-4.

Table 2. Effect of curing time on the Incremental leaching rate of ^{137}Cs from cement (Sample M_1)

Cumulative time leached [days]	Incremental leaching rates $R_n[\text{cm/d}]$	
	30 days cured	60 days cured
1-10	$2.61 \cdot 10^{-6}$	$1.35 \cdot 10^{-6}$
10-30	$3.41 \cdot 10^{-6}$	$3.22 \cdot 10^{-6}$
30-100	$6.30 \cdot 10^{-6}$	$6.00 \cdot 10^{-6}$
100-240	$8.00 \cdot 10^{-6}$	$7.46 \cdot 10^{-6}$

Table 3. Effect of curing time on the Incremental leaching rate of ^{137}Cs from cement (Sample M_2)

Cumulative time leached [days]	Incremental leaching rates $R_n[\text{cm/d}]$	
	30 days cured	60 days cured
1-10	$2.34 \cdot 10^{-6}$	$2.30 \cdot 10^{-6}$
10-30	$2.47 \cdot 10^{-6}$	$2.20 \cdot 10^{-6}$
30-100	$5.30 \cdot 10^{-6}$	$5.10 \cdot 10^{-6}$
100-240	$7.00 \cdot 10^{-6}$	$6.50 \cdot 10^{-6}$

Table 4. Effect of curing time on the Incremental leaching rate of ^{60}Co from cement (Sample M₃)

Cumulative time leached [days]	Incremental leaching rates R_n [cm/d]	
	30 days cured	60 days cured
1-10	$6.04 \cdot 10^{-7}$	$5.90 \cdot 10^{-7}$
10-30	$1.42 \cdot 10^{-6}$	$1.10 \cdot 10^{-6}$
30-100	$4.30 \cdot 10^{-6}$	$3.00 \cdot 10^{-6}$
100-240	$6.00 \cdot 10^{-6}$	$5.83 \cdot 10^{-6}$

4. CONCLUSIONS

All results exhibit practically the same general characteristics. An enhanced initial period of leaching occurs during the first 25-30 days or so, followed by a distinct reduction in the leach rate which is broadly maintained up to the long period of leaching. The leach behaviour of cement-mortar materials can be explained as a combination of two processes; surface wash-off, which is not diffusion controlled, followed by a static diffusion stage. Enhanced initial period of leaching can be explained in terms of a rapid equilibrium being established between spaces present in the surface pores of the Portland cement and ions in solution in the leachant; hence the term wash-off. It is this second stage which is controlled by diffusion and which dominates the long-term leaching behaviour of the material. Under these circumstances the effect of increased curing time on the diffusion coefficient becomes apparent.

In this paper we also prove that increasing amount of bentonite cause a significant reduction in the leaching rate, because of bentonite good sorption characteristics and ion selectivity. Results presented in this paper are examples of results obtained in a 30-year concrete testing project which will influence the design of the engineer trenches system for future central Serbian radioactive waste storing centre.

REFERENCES

1. H. Christensen, Cement solidification of BWR and PWR bead resins, *Proc. Int. Conf. Waste Management '81, Tucson, USA*, 1981, pp. 545-548.
2. T. Matschei, B. Lothenbach and F.P. Glasser, The role of calcium carbonate in cement hydration, *Cement and Concrete Research*, **37** (4), 551-558 (2007).
3. T. Matschei, B. Lothenbach and F.P. Glasser, The AFm phase in Portland cement, *Cement and Concrete Research*, **37** (2), 118-130 (2007).
4. H. Christensen, Leaching of cesium from cement solidified BWR and PWR bead resins, *Nuclear and Chemical Waste Management*, **3** (2), 105-108 (1982).
5. R.W. Crawford, F.P. Glasser, A.A. Rahman, M.J. Angus and C.E. McCulloch, Diffusion mechanisms and factors affecting leaching of ^{134}Cs from cement-based waste matrices, *Radioactive Waste Management and the Nuclear Fuel Cycle*, **6** (2), 177-196 (1985).
6. E.D. Hespe, Leach testing of immobilized radioactive waste solids - A proposal for a standard method, *Atomic Energy Review*, **9** (1), 195-207 (1971).
7. I. Plečaš, A. Perić and S. Pavlović, Effect of curing time on the fraction of ^{137}Cs leached from cement matrix, *Journal of Radioanalytical and Nuclear Chemistry-Letters*, **200** (1), 25-29 (1995).
8. I. Plečaš, R. Pavlović and S. Pavlović, Effect of curing time on the fraction of ^{137}Cs from cement matrix, *Proc. 6th Int. Symp. on Conditioning of Radioactive Operational-Decommissioning Wastes (KONTEC-2003), Berlin, Germany*, 2003, pp. 809-811.
9. F.P. Glasser, Fundamental aspects of cement solidification and stabilisation, *Journal of Hazardous Materials*, **52** (2-3), 151-170 (1997).

EFEKAT VREMENA OČVRŠĆAVANJA NA FAKTOR IZLUŽIVANJA ^{137}Cs IZ KOMPOZICIJE CEMENT- JONOIZMENJIVAČKA SMOLA-BENTONIT

Ilija Plećaš, Slavko Dimović

U cilju procene bezbednosti konačnog odlagališta radioaktivnih otpadnih materijala cementnim postupkom, ispitivano je vreme očvršćavanja uzoraka i vreme izluživanja ^{137}Cs iz uzoraka cement-jonoizmenjivačke smole Bentonit, u skladu sa metodom preporučenom od strane IAEA. Uslovi očvršćavanja i vreme očvršćavanja pre ispitivanja brzine izluživanja su od izuzetne važnosti za proučavanje izluživosti uzoraka i hidrataciju cementnih materijala, kao i mogućnost ispitivanja hidratacije na zapušavanje pora cementnih uzoraka, čime se smanjuje brzina izluživanja radionuklida. Merenje je trajalo 240 dana i izračunat je prirast vrednosti izluživanja $R_n[\text{cm/d}]$ radionuklida ^{137}Cs . Rezultati ovih istraživanja su deo 30-godišnjeg rada na pripremi projekta izgradnje trajnog odlagališta radioaktivnog otpada tipa plitko ukopanih betonskih inženjerskih tranšeja.

Ključne reči: cement, radioaktivni otpad, radionuklid, izluživanje, beton